

Secondary Chemical Containment

ID: 10121

Industry: Chemical & Petrochemical
Application: TCC-Tanks and Chemical Containment Areas
Substrate: Concrete
Products: Belzona 4111 (Magma-Quartz), Belzona 4311 (Magma CR1), Belzona 4911 (Magma TX Conditioner)

Customer Location: Decatur, AL
Application Date: November 2021

Problem

This secondary chemical containment had never been coated and has seen several spills over the last few years. This has caused severe damage to the concrete and sump pit area where water/chemicals had stood until it was pumped out.



Before picture of the containment area where you can see the damaged areas.



Close up of the sump pit area. Here you can see how bad the concrete had deteriorated between the sump pit and exterior wall of the containment.



In this picture, after we removed all loose and damaged concrete we thoroughly cleaned the area to be repaired with 100% MEK and began to prep the surface with grinders and needle guns. Once we achieved the correct surface prep we applied Belzona 4111



Once the repair was complete we applied 2 coat of Belzona 4311. In this application we perform a yearly inspection for the client.

Application Situation

For this application we were able to save the customer several days of down time by being able to work while the process was going. Each day they would have been would have cost over three million dollars. We were able to perform this work with no down time and completed in five days.

Application Method

In this project we used several types of equipment such as walk behind grinders, hand held grinders and needle guns to prepare the

For more examples of Belzona Know - How In Action, please visit <https://khia.belzona.com>

ISO 9001:2015
 FS 695214
 ISO 14001:2015
 EMS 695213

Belzona products are
 manufactured under an ISO
 9000 Registered Quality
 Management System.

www.belzona.com


BELZONA[®]
 Repair • Protect • Improve

surface. We also used speciality designed trowels to contour the edges of the sump pit for the grating and the two inch cove around the bottom interior wall.

Belzona Facts

Cost savings for this project exceeded three million dollars due to no down time and material cure time which allowed us to complete the project in just five days. The alternative was to cut out and remove the bad concrete areas rebuild the sump pit and wait 28 days for the concrete to cure then to apply a coating.

For more examples of Belzona Know - How In Action, please visit <https://khia.belzona.com>

ISO 9001:2015
FS 695214
ISO 14001:2015
EMS 695213

Belzona products are
manufactured under an ISO
9000 Registered Quality
Management System.

www.belzona.com

