

BELZONA SAVES TIME IN A BATTERY STATION

ID: 5562

Industry: General Industry
Application: FPA-Floor Problem Areas
Substrate: Concrete
Products: * Belzona 4131 (Magma-Screed) ,
* Belzona 5811 (Immersion Grade) ,

Customer Location: Duncan, Oklahoma, USA
Application Date: February 2015

Problem

The main path for the current battery forklift was worn to the point where the lift could no longer be used to exchange charged batteries onto the forklifts. The worn pathways were 1/2" to 3/4" deep and 6" wide from the existing elevation. Due to extreme wear from the battery forklift and acid spills on concrete, the 6" wheels had created ruts in the existing concrete, causing damage to the battery forklift that required monthly repairs. The objective was to rebuild 8" wide runways for the battery forklift and provide a protective coating for the Battery acid from runways.



Photograph Descriptions

- * Battery forklift in place ,
- * Battery forklift removed; full view of battery station ,
- * 8" battery forklift runways being rebuilt with Belzona 4131 ,
- * Completed project before battery forklift was reinstalled ,

Application Situation

Battery station for a million square foot distribution warehouse that operates 24/7.

For more examples of Belzona Know - How In Action, please visit <https://khia.belzona.com>

ISO 9001:2015
FS 695214
ISO 14001:2015
EMS 695213

Belzona products are
manufactured under an ISO
9000 Registered Quality
Management System.

www.belzona.com


BELZONA
Repair • Protect • Improve

Application Method

The application was carried out in accordance with Belzona Know-How System Leaflet FPA-1 and FPA-3.

Belzona Facts

The worn battery forklift runways were widened and rebuilt with Belzona 4131 and the surrounding concrete substrate was coated with Belzona 5811 to prevent further battery acid corrosion to concrete. Other products were used to rebuild track runways but quickly failed. The traditional repair option was to cut out concrete and replace. The repair estimated to cost an average of \$75,000 and take 28 plus days of shutdown. Note: the cost wasn't the issue as much as the downtime. The Belzona solution provided a cost savings of \$58,000 and reduced downtime by 25 days when compared to the traditional repair method. Actual downtime: this project was completed on a scheduled weekend shutdown for other repairs within the facility.

For more examples of Belzona Know - How In Action, please visit <https://khia.belzona.com>

ISO 9001:2015
FS 695214
ISO 14001:2015
EMS 695213

Belzona products are
manufactured under an ISO
9000 Registered Quality
Management System.

www.belzona.com

