# **Belzona 3121 Relines Valley Gutter at Large Hospital**

ID: 8689

Industry:Buildings & StructuresCustomer Location: Nottingham, UKApplication:RPA-Roof Problem AreasApplication Date: December 2021

Substrate: Steel valley gutter with previous failed coatings

Products: \* Belzona 3121 (MR7),

\* Belzona 9331,

#### Problem

The leaks were worsening and the client tried a number of solutions and a number of contractors, all without a good result. Belzona was approached by a contractor and Belzona 3131 was specified, but was later changed to Belzona 3121 (MR7).









## **Photograph Descriptions**

- \* 1. Before Application,
- \* 2. During Application,
- \* 3. After Application,
- \* 4. Completed Gutter and Downpipe,

## **Application Situation**

A single valley gutter has repeatedly leaked over a crucial part of the hospital. It was metal/plastisol construction with sealed joints every 3 metres. The total area surface area was 12 square meters.

#### **Application Method**

All surfaces were prepared in line with the Belzona 3121 Instructions For Use. The first coat was applied to the prepared substrate along with Belzona 9331 reinforcing sheet, ensuring the fibrous side of the sheet was facing down. The product was overlapped on either side of the central run by approximately 0.5" (12.5mm). This was applied in accordance with Belzona System Leaflet RPA-06.

For more examples of Belzona Know - How In Action, please visit https://khia.belzona.com

ISO 9001:2015 Belzona products are
FS 695214 manufactured under an ISO
ISO 14001:2015 9000 Registered Quality
EMS 695213 Management System.

BELZONA®
Repair • Protect • Improve

#### **Belzona Facts**

This work was requested by a local, trusted contractor who had carried out Belzona applications at the hospital previously, though for water storage tanks. The original specification of Belzona 3131 was changed to Belzona 3121 to meet the projects time demands. Belzona showed full flexibility with this application, with all parties working closely together to bring a rapid solution which should last for many years. Despite the impact of Covid, Belzona still achieved the client's wishes through teamwork with internal departments and trusted contractors on time, on budget.